BRUHATH BENGALURU MAHANAGARA PALIKE,DASARAHALLI ZONE

Office of Executive Engineer

SCHEDULE -B

Name Of Work: Roads and Footpath Maintenance in ward no 15

Sl. No	Descrption of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	63.00	250.00	
2	Supplying fixing precast reinforement concrete slabs 10cm thick including cost of reinforecemet as per design and drawing material cost transpotation hire charges of machinery. Machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges labour charges of cost of all materials. etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	284.40	1700.00	

Signature of Contractor

Executive Engineer
Dasarahalli Division